

香港中樂團工程招標公告

招標項目：為 2026 國際笙簧節「笙生不息- 千簧和鳴」笙簧馬拉松現場 4K 直播及錄影, 音響工程及錄音, 舞台搭建, 燈光, AV 等器材及操作。

項目內容：合約工程包括如下（可選擇投標其中一個或多個項目。請注明投標項目）：

項目一：舞台搭建, 燈光, AV 等器材及操作

Item #	Description	QTY	Unit
A	Marquee & Tent		
1	<u>3m x 3m Pagoda Marquee(Control Panel)</u>	4	sets
	- Color: White		
	- Include White PVC Roof, Side Wall, Concrete Block for counterweight		
2	<u>10m x 10m Tent</u>	1	set
	- Color: White		
	- Include White PVC Roof, Side Wall, Concrete Block for counterweight		
3	<u>3m x 3m Pop-Up Marquee</u>	34	sets
	- Color: White		
	- Include White PVC Roof, Side Wall, Sandbags for counterweight		
4	<u>License and Certifications</u>	1	job
	- Registered Structural Engineer reports and certificates		
5	<u>Manpower & Transportation</u>	1	job
	- Include sufficient manpower for set up & dismantle		
	- Include 2-way transportation & rubbish disposal		
B	Furniture		
1	<u>Office Container x 9</u>		
	- Working Table	27	nos
	- Folding Chair	54	nos
2	<u>Marquee x 12</u>		
	- Working Table	24	nos
	- Folding Chair	48	nos
3	<u>VIP Seating</u>		
	- Folding Chair	40	nos

香港中樂團工程招標公告

4	<u>Info Booth x 2 (Outside the Venue)</u>		
	- Working Table	6	nos
	- Folding Chair	12	nos
5	<u>Check-in Booth x 3 (Outside the Venue)</u>		
	- Working Table	9	nos
	- Folding Chair	18	nos
6	<u>First-aid x 1 (Outside the Venue)</u>		
	- Working Table	2	nos
	- Folding Chair	4	nos
7	<u>Opening Ceremony (Central Square)</u>		
	- Table with Table Cloth	4	nos
	- Folding Chair	30	nos
8	<u>1.8m metal barrier</u>	120	nos
9	<u>Manpower & Transportation</u>	1	job
	- Include sufficient manpower for set up & dismantle		
	- Include 2-way transportation & rubbish disposal		
C	Musician Equipments		
1	<u>Performers Chair</u>	90	pcs
	- Banquet Chair in Black		
2	<u>Music Stand</u>	80	pcs
	- Color: Black		
3	<u>Manpower & Transportation</u>	1	job
	- Include sufficient manpower for set up & dismantle		
	- Include 2-way transportation & rubbish disposal		
D	Electricity		
1	<u>Power Distributions Power Distribution</u>	1	job
	- 400A Powerlok cable (1C 185sqmm*4 + 1C 95sqmm*1 E) 5m		
	- 400A powerlok in to 2x 200A powerlok out (SLY)		
	- 200A Powerlok Cable (1C 95sqmm*5) 5m		
	- 200A Camlok Cable(1C 95sqmm*5) 30m		
	- 200A DB (E) Powerlok in (4x 63A out) SLY		
	- 41KG/PCS 600mm X 500mm X 540mm		
	- 200A DB (F) Powerlok in (8x 32, 2x 63, 1x 125A outdoor)		
	- 63A TPN - Indu - (2x 32A RCBO TPN Cee) outdoor		
	- 63A 5pin Ceeform (5G16sqmm cable) 30m		

香港中樂團工程招標公告

	- 63A 5pin Ceeform (5G16sqmm cable) 10m		
	- 32A 5pin Ceeform Cable (5G6sqmm) 30m		
	- 32A 5pin Ceeform Cable (5G6sqmm) 10m		
	- 32A TPN to 6x 16A SPN (RCBO, outdoor) (SLY)		
	- 16A 3pin Ceeform Cable (3G2.5sqmm) 30m		
	- 16A 3pin Ceeform Cable (3G2.5sqmm) 10m		
	- 24" Twin Fluorescent		
	- 400W Waterproof HID Flood w/ Hook Clamp		
	- Rubber Cable Ramps (5-channel)		
2	<u>Electricity Item for Marquee Setup</u>	1	job
	- Include 13amp socket x1, light tube x2 for each marquee		
3	<u>Manpower & Transportation</u>	1	job
	- Include sufficient manpower for set up & dismantle		
	- Include 2-way transportation & rubbish disposal		
	- Include electrician and general crew on show day		
	- Include 9ton truck, 5.5 ton truck and van transportation		
E	Hardware Production		
1	<u>Main Stage - Stage Platform & Ground Support</u>	1	set
	- 1 x Platform with carpet, size: 19504mmW x 12803mmD x 1000mmH		
	- 1 x Ground support system, size: 42000mmW x 12000mmD x 10000mmH		
	- On Stage Riser		
	- 1 x White Rain cover		
	- 1 x Mesh Banner on Stage		
2	<u>Estimated Concrete blocks (Final quantity subject to upon the RSE calculation)</u>	40	pcs
3	<u>VIP Platform</u>	1	set
	- 1 x Platform with carpet (size: 10974mmW x 3657mmD x 400mmH & 600mmH)		
	- Including Handrails and Staircase		
4	<u>Control Panel</u>	1	set
	- 1 x Platform with carpet (size: 14632mmW x 3657mmD x 1800mmH)		
	- Including Handrails and Staircase		
5	<u>Manpower & Transportation</u>	1	job
	- Include sufficient manpower for set up & dismantle		
	- Include 2-way transportation & rubbish disposal		

香港中樂團工程招標公告

6	<u>Mechanisms</u>	1	job
	- Include 2 x Forklift, 1x RB Crane		
7	<u>Generac Light Tower</u>	1	set
8	<u>Main Entrance Archway</u>	1	job
	-Size: 8300mmW x 400mmD x 4150mmH		
	-Size: 12050mmW x 400mmD x 4150mmH		
F	AV Equipment		
1	<u>Lighting System Package</u>		
	-Arri Skypanel	16	sets
	-MA3 Control	2	set
	- Accessories	1	job
	- Operator Standby	1	job
	- Technician	2	pax
2	<u>Video System</u>		
	- Outdoor LED wall (side wing), size 7mW*4mH	2	sets
	- Macbook Pro	1	set
	- Cue mon	2	pcs
	- Barco control	1	set
	- Accessories	1	job
	- Operator Standby	1	job
	- Technician	2	pax
3	<u>Technical Crew</u>	1	job
	- Technicians Standby		
	- Manpower for Setup and Dismantle		
G	Office Container		
1	<u>20' Movable Container Office</u>	9	nos
	- Including AC		
	- Include 2-way Transportation & Installation (With overnight craning and manpower for setup and dismantle)		
2	<u>Extinguishers, Emergency Light and Exit Lightbox</u>	9	sets
H	Artwork Production		
1	8m Truss Entrance	2	nos
	- Material: Vinyl Banner, size: 8000mmW x 1000mmH		

香港中樂團工程招標公告

2	12m Truss Entrance	2	nos
	- Material: Vinyl Banner, size: 12000mmW x 1000mmH		
3	Container Signage	9	nos
	- Material: Foamboardm, size: A4		
4	Marquee Fascia with Frame	14	nos
	- Material: Foamboard, size: 3000mmW x 600mmH		
5	Site Map (2 x East village, 2 x KTSP area)	4	nos
	- Size: 2000mmW * 500mmD * 2000mmH		
	- Material: R8 system with 3-sided foamboard graphic		
6	Signage Stand	20	nos
	- Size of stand: 650mmW * 400mmD * 1090mmH		
	- Size of graphic: 600mmW * 1000mmH		
7	3500mmH Double-side Flag	20	nos
	- Size of graphic: 600mmW * 1600mmH		
8	5000mmH Double-side Flag	4	nos
	- Size of graphic: 520mmW * 2500mmH		
9	Barricade Banner	15	nos
	- Size: 2075mmW * 770mmH		
10	Customised Badge with Lanyard	1,800	sets
11	Paper Wristband	2,000	nos
12	Coloured PVC rolls (Zoning)	1	job
13	<u>Manpower & Transportation</u>	1	job
	- Include sufficient manpower for set up & dismantle		
	- Include 2-way transportation & rubbish disposal		
I	Event Management		
1	<u>Pre-event Programme Management</u>	1	job
	- Overall Creatives, Conceptualization and Execution		
	- Dedicated Project Team for Overall Project Management & Coordination for Pre-event, On-site and Post Event		
	- Preparation and Monitoring of Overall Project Timeline		

香港中樂團工程招標公告

	- Arrange and Attend Pre-event Meetings, Site Inspections and Technical Tests		
	- Liaison with Relevant Parties		
2	<u>Floor Marking</u>	1	job
	-		
3	<u>Noise Control (21-22 March 2026)</u>	1	position
	- Include noise monitoring plan and report		
	*Subject to final location		
J	Certificate and License		
1	<u>RSE Calculation Report</u>	1	job
	-		
2	<u>FS251</u>	1	job
	-		
3	<u>WR1</u>	1	job
	-		
A	Optional Item		
1	<u>Portable Toilet (Sitting Style)</u>	10	nos
	- Flushing system / Hand washing sink / Urinal / Concealed toilet bowl / With 2 rolls of toilet paper		
	- Available Date: 21 - 22 March 2026		
	- Include 2 toilet attendant for 2 days (21 - 22 March 2026)		

香港中樂團工程招標公告

項目二：4K 直播及錄影

Item	Content	Quantity
Switcher	For A HVS-1200	1
Camera	Sony HDC 4300 4K System Camera	3
	Sony HDC 5500 4K System Camera	2
	Sony ILME-FX3	3
	Sony Burano	1
	Sony PXW-FX9	1
	Drone	1
	INCAM SMPTE Convertor	4
Wireless	LiveU 4K wireless video	3
	CVW 4K wireless video	1
Lens	Fujinon UA125x8BESM-S35A	1
	Fujinon Cabrio ZK4.7X19-SAF T2.9 – 19-85mm	1
	Fujinon HA 14x4.5 BERD	4
	Fujinon UA 22x8BERD-S8	2
	Sony 28-70mm f3.5-5.6	3
Support	HD Tripod	1
	Vinten Osprey Pedestal	1
	Jimmy Jib	2
	Tripod	4
	Track	1 Lot
	DJI Gimbal	3
GFX	Mac with Propresenter	1
Monitor	Sony 49” LCD for Multiviewer	1
	17” HDSDI Monitor	2
	9” HDSDI Monitor	2
	Osee RMS4342 4 In 1	2
VTR	AJA KiPro Ultra	7
Audio	Yamaha CL 5	1
	Yamaha MSP3	2
Intercom	Telex Zeus II 24x24 Matrix	1 Set
	Hollyland Solidcom C1	1 Set

香港中樂團工程招標公告

Item	Content	Quantity
Cable	Camera Fiber	1 Lot
	Video, Audio, Power Cable	1 Lot
	Video Fiber	1 Lot
Power	UPS	1 Lot
Transportation	Round Trip Transportation	1 Job
4K Streaming	Wirecast Gear 4K	1
	Science Image VELA-SDI	1
	UniFi / Mikrotik Network Router	1

香港中樂團工程招標公告

項目三：音響工程及錄音

ITEM	Content	Brand/Model	Quantity
<i>Speaker System</i>			
Main Speaker	Main Line-array Speaker	d&b J8	28
		d&b J12	8
Main Sub		B22	6
Front Fill		d&b Y10P	9
Stage monitor		M4 monitor	10
Amplifier		D80 Amplifier	20
Soundscape Processor		d&b DS100	1
Audio Network Bridge		d&b DS10	2
Console		Digico 338	1
Stage Rack		SD-Rack (32Bit)	2
Fibre cable		100M fibre	2
		5M fibre	1
Microphone	Condensor Microphone	For musical Instrument	90
	Dynmaic Microphone	For musical Instrument	20
	Loom & Cable		1 Lot
	Wireless handheld		8
	Mic stand		110

香港中樂團工程招標公告

ITEM	Content	Brand/Model	Quantity
Kick-off area	Main Speaker	d&b Y7P	4
	Sub	d&b Ysub	2
		Console Yamaha CL5	1
		Wireless Handheld	6
		Wireless Mic for MI	6
		Condenser mic	8
Hamonica Area	Main Speaker	d&b Y7P	6
		Console Yamaha CL5	1
		Wireless Handheld	12
Marathon	Wireless	Wireless Set for Camera	2
		Boom arm	2
		Gun Mic	2

香港中樂團工程招標公告

預計施工期：2026年3月18日至21日

演出日期：2026年3月22日

拆卸日期：2026年3月23日

施工地點：香港啟德體育園東營

項目負責：舞台技術及製作高級經理 曾浩然先生

電話：852-3185 1642

電郵：ray@hkco.org

截標日期：2026年2月27日(星期五)中午12時

投遞標書：投標者必須提供圖紙及按招標書內指定物資提供報價，如未能提供相同物料必須清楚說明替代物料資料。投標書放置信封內密封，並在信封面清楚註明「香港中樂團工程招標 2026」，並於**2026年2月27日(星期五)中午12時前**把投標書放入香港上環皇后大道中345號上環市政大廈7樓行政部門外投標書箱內。投標者必須在截標時間前把投標書放入本招標箱內。**逾期遞交或未有放入指定投標箱的投標書，概不受理。**

備註：所有使用之物料、式樣及內容，須於施工前與香港中樂團確認。

香港中樂團不一定採納任何一份投標書，即使該份投標書索價最低。

香港中樂團有權與任何投標者商議批出合約的條款。